



Construction site activities — phase-based + trade-based reference

Canonical reference for what happens on a construction site, organized two ways: by **phase** (chronological) and by **trade** (people-shaped). Used as source-of-truth for:

- v1.2 sub-contractor **work_type** dropdown (17-trade taxonomy at the end)
- v1.2 Work Order PDF (scope categorization)
- Future v2 reports (filter by trade)
- Onboarding new engineers / partners — domain map in 10 minutes

Last updated 2026-05-22

Part 1 — Phase-based view (chronological)

Markers: ☒ Storey covers this today · ● v1.2 in development · — out of scope

A. Pre-construction & site setup (weeks 1–3 of a project)

Activity	Storey today?
Land survey, boundary marking	—
Soil / strata testing	—
Site office + labour quarters + material store setup	— (could be a site detail field)
Utility connections — power, water, sanitation	—
Compound wall / temporary fencing	☒ trackable as a Task
Material procurement plan (initial BOQ)	● v1.2 (budget tracking)
Sub-contractor sourcing + scope freezing	● v1.2 (onboarding)
Workforce planning (head-count + skills)	☒ Workers module
Insurance + statutory registrations (PF, ESI, labour licence)	—

B. Earthwork & foundation (weeks 3–8)

- Excavation (manual / JCB) — ☒

- Cutting and filling — ✓
- Soil compaction — ✓
- Foundation pit digging — ✓
- Shoring / strutting — ✓
- Dewatering (monsoon-critical in NE) — ✓
- PCC (footing concrete) — ✓
- Reinforcement (rebar) cutting, bending, tying — ✓
- Footing casting — ✓
- Column starters — ✓
- Plinth beam casting — ✓
- Anti-termite treatment — ✓
- Damp-proof course (DPC) — ✓

C. Superstructure (RCC) (weeks 6–20+, per floor)

- Column casting (each floor) — ✓
- Beam casting — ✓
- Slab casting — ✓ *(the iconic milestone — Storey supports Task photos for this)*
- Staircase — ✓
- Lintel + chajja — ✓
- Curing schedule + verification — ● *Storey could prompt this via tasks; not automated yet*

D. Masonry & roofing (weeks 12–24)

- Brickwork (external + partition) — ✓
- Block work (lightweight / AAC) — ✓
- Stone masonry — ✓
- Sloped roof (CGI / Mangalore tile — common in NE) — ✓
- Waterproofing — ✓
- Insulation — ✓

E. MEP — Mechanical / Electrical / Plumbing (parallel to F, weeks 16–30)

- Conduit laying (electrical, pre-plaster) — ✓
- Wiring + switchboards + DBs — ✓
- Earthing — ✓
- Inverter / generator integration — ✓
- Underground drainage, vent pipes, soil pipes — ✓
- Water supply lines — ✓
- Plumbing fixtures (basins, WCs, taps) — ✓
- Septic tank / soak pit — ✓

F. Finishing (weeks 22–36)

- Internal plaster — ☒
- External plaster — ☒
- Putty / smoothing — ☒
- Flooring — sub-floor leveling — ☒
- Tile / marble / vitrified laying — ☒
- Skirting — ☒
- Outdoor paving (pavers, kota stone, IPS) — ☒
- Door & window frame fixing — ☒
- Shutter installation + glazing — ☒
- Locks + fittings — ☒
- Painting — primer, putty, paint — ☒
- POP / false ceiling — ☒
- Wood polish / textures — ☒

G. External works (weeks 30–40)

- Storm water drainage — ☒
- Compound paving — ☒
- Landscaping / horticulture — ☒
- Gates + boundary wall — ☒
- Signage — ☒

H. Daily site operations (*every day*)

Activity	Storey today?
Worker attendance	✓
Daily log / progress report	✓ (with photo)
Material receipt + GRN	✓
Material allocation to work	✓ (since v1.1.5)
Material transfer between sites	✓ (4-stage flow)
Equipment issue + return	✓
Equipment maintenance log	● <i>partial — v2 enhancement</i>
Petty cash + site expenses	✓
Vehicle / transport coordination	— <i>no logistics module</i>
Visitor log	—
Quality checks (slump test, cube test, level)	— <i>v2 candidate</i>
Photo documentation	✓
Daily huddle / standup notes	— <i>could fit Daily Log</i>

I. Project coordination (*weekly + ad-hoc*)

Activity	Storey today?
Drawings / RFI management	— <i>v2 candidate</i>
Variation / change orders	● v1.2 (Variation Orders for sub-contractors)
Sub-contractor coordination	● v1.2
Vendor / supplier follow-up	— <i>v2 candidate</i>
Client communication log	—
Payment milestone tracking	● v1.2 (sub-contractor payment ledger)
Running bills + certification	● v1.2 partial
Weekly progress review	✓ Reports
Project timeline / Gantt	— <i>v1.x backlog</i>

J. Safety & compliance (*daily + statutory*)

Activity	Storey today?
PPE issue & sign-off	— <i>v2 candidate</i>
Safety drills + records	—
Fire safety checks	—
Site safety officer rounds	● <i>could be a Task</i>
Govt inspections (PWD, electrical, fire, pollution)	—
Statutory compliance (PF, ESI, labour licence renewals)	—

K. NE-India specific context

Activity	Storey today?
Monsoon planning (Jun–Sep heavy rain, work paused on certain activities)	— <i>v2: weather-aware tasks</i>
Labour migration (tea-garden cycles, festival season)	—
Brick supply from local kilns	✅ via Materials
Sand mining permits (state-wise rules)	—
Transport — NH-37 / NH-2 logistics, mountain road delays	—

Part 2 — Trade-based view (people-shaped)

Each trade below corresponds to a typical sub-contractor scope.

L1. Civil / structural trades

Trade	What they do	Phase(s)	NE-India term
Excavation / earthwork	JCB ops, manual digging, soil shifting	B	Mati ka kaam
Bar bending / rebar	Cutting, bending, tying steel	B, C	Sarbandhwala
Form work / shuttering	Plywood + props for casting columns/beams/slabs	C	Shuttering wala
RCC / concreting	Pour, vibrate, level, cure	B, C	RCC mistri / Concrete contractor
Mason — brickwork	Brick + mortar walls	D	Raj mistri
Mason — block work	AAC / concrete block walls	D	Block mistri
Mason — stone	Random rubble, dressed stone	D	Patthar mistri
Plastering	Internal + external, sand-cement	F	Plaster mistri
Roofing — sloped	CGI, Mangalore tile, GI sheet	D	Tin / chal mistri
Waterproofing	Terraces, bathrooms, basements	D, F	Waterproofing contractor

L2. MEP trades

Trade	What they do	Phase(s)	NE-India term
Electrical — wiring	Conduit, wiring, switchboards, DB	E	Electrical mistri / Bijli wala
Electrical — earthing	Pits, copper plate, strip	E	(same)
Electrical — fixtures	Lights, fans, plugs, switches	E, F	(same)
Solar / inverter	Panel install, battery, inverter integration	E	Solar contractor
Plumbing — water supply	Pipes, taps, valves, overhead tank	E	Plumbing mistri / Naloowala
Plumbing — drainage	Soil pipes, vent pipes, traps	E	(same)
Plumbing — fixtures	WCs, basins, kitchen sinks	E, F	(same)
Septic tank / soak pit	Excavation + masonry combo	E	(same)
HVAC	AC, ducting, chiller	E	HVAC contractor (<i>rare in SMB NE-India</i>)
Fire safety	Sprinklers, hydrants, fire panels	E	Fire contractor (<i>commercial only</i>)

L3. Finishing trades

Trade	What they do	Phase(s)	NE-India term
Tiling — floor	Vitrified, ceramic, anti-skid	F	Tile mistri / Marble mistri
Tiling — wall	Kitchen, bathroom, dado	F	(same)
Marble / granite	Slab, polishing, edging	F	Marble mistri
Painting — internal	Primer, putty, emulsion	F	Painter / Rang mistri
Painting — external	Weatherproof, texture	F	(same)
POP / false ceiling	Gypsum ceiling, cove lighting	F	POP mistri
Wallpaper / texture	Decorative finishes	F	(rarely standalone)
Wood polish	French polish, melamine	F	Polish mistri

L4. Joinery / carpentry trades

Trade	What they do	Phase(s)	NE-India term
Carpentry — door/window frames	Sal wood / engineered frames	F	Carpenter / Kaath mistri
Carpentry — shutters	Flush doors, panel doors	F	(same)
Carpentry — built-ins	Wardrobes, kitchen cabinets, shelves	F	(same)
Wooden flooring	Strip / engineered planks	F	<i>(specialised contractor)</i>

L5. Metal trades

Trade	What they do	Phase(s)	NE-India term
Steel fabrication / welding	Railings, gates, grills, trusses	C, F, G	Welding mistri / Lohaar
Aluminum	Windows, sliding doors, façade	F	Aluminum contractor
Glass	Glazing, shower partitions, façade	F	Glass contractor
Structural steel	Trusses, columns, beams (pre-fab)	C	Steel fabricator

L6. Site services (specialist support, not stand-alone scope)

Trade	What they do	Phase(s)
Scaffolding contractor	Erects + dismantles	C, D, F
Crane / hoist operator	Material lifting	C, D
Stone polishing	Marble / kota grinding	F
Anti-termite treatment	Pre + post construction	B, F
Pest control	Final hand-over	G
Landscape / horticulture	Lawn, plants, irrigation	G

L7. Specialty / less-common in SMB NE-India

Trade	When you'd see them
Acoustic	Auditoriums, recording studios
Cladding	Premium façades — stone, ACP, composites
Lift / elevator	4+ floor buildings — usually mfr-installed (Otis, Kone, Schindler)
Swimming pool	Resorts, premium villas
Smart-home / automation	Premium residential, last 2 years only

Part 3 — Locked taxonomy for v1.2 `subcontractor.work_type`

17 entries — enough to cover ~95% of NE-India SMB jobs without making the dropdown unusable on a phone.

1. Excavation / earthwork
 2. RCC / concreting
 3. Rebar / bar bending
 4. Form work / shuttering
 5. Masonry (brick + block)
 6. Plastering
 7. Waterproofing
 8. Roofing
 9. Electrical (wiring + fixtures)
 10. Plumbing (water + drainage)
 11. Tiling / flooring
 12. Painting
 13. Carpentry / joinery
 14. Steel fabrication / welding
 15. POP / false ceiling
 16. Aluminum / glass
 17. Other ← always the safety valve

Deliberately excluded from v1.2 (use "Other" until a paying customer asks):

- HVAC, Fire safety, Lift / elevator — rare in SMB NE-India
 - Sub-trade-level granularity (e.g. "Plumbing — water" vs "Plumbing — drainage") — one category covers both
 - Solar / smart-home / automation — high-end residential, not the beachhead
 - NE-India regional terms in the UI — per CLAUDE.md, English-default; Hindi/Assamese is a future Settings toggle
-

What's currently missing from Storey (*honest gaps*)

Storey covers ~70% of daily ops well today. The big gaps to evaluate post-v1.2:

1. **Quality assurance** — slump tests, cube tests, level surveys. Real contractors keep these in notebooks. *Could be a v2 lab/QA module.*
2. **Compliance / statutory** — PWD inspections, electrical sign-off, labour licences. *High-pain, low-glamour. v2 candidate.*
3. **Logistics / transport** — vehicle dispatch, fuel logs, driver attendance. *Sizable.*
4. **Drawings / RFI** — most sites still pass paper drawings around. Could be a big differentiator. *v2 or v3.*
5. **Client communication** — site → contractor → client thread. *Could be a v2 wedge for higher-value contracts.*

The 70% Storey has is the right 70% — it's the daily-bread work that supervisors actually do every day. The remaining 30% is mostly *episodic* (compliance) or *enterprise-grade* (RFI, drawings) — not what the NE-India SMB beachhead needs at v1.